K.S. ENGINEERING WORKS

PRECISION MACHINING, TURNED COMPONENTS & FABRICATION

FA-3, Plot No 1, S.S.I Unit, MIDC, Ambad, Nashik, Maharashtra - 422010

GSTIN: 27AQUPK5416E1ZM | **PAN:** AQUPK5416E

Ph: +91 9890241776 | **Email:** ksengineeringworks2005@gmail.com

Quotation No: QT-2026-0042/R2

Quotation Date: 17-Oct-2026

Client RFQ Ref: TECNOTRANS/RFQ-9821

Validity: 30 Days (Upto 16-Nov-2026)

QUOTATION PREPARED FOR (BILLED TO)

TECNOTRANS ELECTRIC AND ENGINEERING SERVICES PRIVATE LIMITED

Plot No. 1388/3072, BS Bhawan, Balianta Bazar Road, Near Shakti Paradire Apartment, Hansapal, Bhubaneshwar, Khordha, Odisha - 752101

GSTIN: 21AAMCT5739N1ZS | **Kind Attn:** Mr. P. K. Mohanty (DGM - Procurement & Quality)

Phone: 7008342064 | **Email:** tecnotransele@gmail.com

COMMERCIAL DELIVERY & PAYMENT

Payment Terms: 30 Days Credit from Delivery Date

Delivery Period: 2-3 Weeks from Confirmed PO

Freight Basis: Ex-Works Nashik (Freight extra at actuals)

Place of Supply: Odisha (State Code: 21) - Interstate

#	DESCRIPTION OF GOODS & TECHNICAL DRAWING REF	HSN	QTY	UNIT	RATE (₹)	TAXABLE (₹)	IGST	AMOUNT (₹)
1	**Round Copper Terminal Block ø30×25xM12** DWG: KS-2026-C01 Rev B ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	7407	**200**	NOS	310.00	**62,000.00**	18%	**73,160.00**
2	**CNC Precision Rotor Turning Shaft OD 45×185mm** DWG: KS-2026-S12 Rev C ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	8483	**50**	NOS	2250.00	**1,12,500.00**	18%	**1,32,750.00**
3	**Laser Cut Transformer Mounting Bracket Plate** DWG: BRK-SS-2026-09 ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	7326	**120**	NOS	750.00	**90,000.00**	18%	**1,06,200.00**
4	**Machined Phosphor Bronze Bush ID 35×50×60L** DWG: BSH-PB-104 Rev A ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	8483	**40**	NOS	1150.00	**46,000.00**	18%	**54,280.00**
5	**Copper Terminal Busbar Link 40×5×150mm Plated** DWG: BUS-CU-55 ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	7407	**100**	NOS	442.00	**44,200.00**	18%	**52,156.00**
6	**Hardened Pinion Gear Shaft OD 60×220mm** DWG: SFT-EN24-88 Rev B ↳ See Annexure-I (Page 2) for 8-Column Technical Specification Matrix	8483	**30**	NOS	3450.00	**1,03,500.00**	18%	**1,22,130.00**

AMOUNT CHARGEABLE IN WORDS

Five Lakh Forty Thousand Six Hundred and Seventy-Six Rupees Only

Bank Details: YES BANK LTD | **A/C:** 00458900012345 | **IFSC:** YESB0000045 (Nashik)

Total Taxable Value: ₹4,58,200.00

Integrated Tax (IGST @ 18%): ₹82,476.00

NET QUOTATION TOTAL: ₹5,40,676.00

TERMS & CONDITIONS:

1. **Validity:** Rates valid for 30 days. Complete technical specifications in Annexure-I (Page 2) form an integral part of this offer.
2. **Quality & QA:** Inspection Report and Material Test Certificate (MTC 3.1) will be supplied along with finished materials.
3. **Jurisdiction:** Subject to Nashik (Maharashtra) jurisdiction.

FOR K.S. ENGINEERING WORKS

Authorized Signatory

ANNEXURE - I : TECHNICAL SPECIFICATIONS & COSTING MATRIX

#	ITEM DESCRIPTION & DRAWING	MATERIAL GRADE & STANDARD	INPUT & NET WEIGHT	BASE METAL & ESCALATION	MACHINING & HEAT TREATMENT	SURFACE & TESTING NORMS	QUOTED RATE (₹)
1	**Round Copper Terminal Block ø30×25xM12** DWG: KS-2026-C01 Rev B Size: **30mm x 25mm x M12 thk**	**EC Grade Copper 99.9% IS 1897**	Gross In: **0.240 Kg** Net Fin: **0.180 Kg** Scrap: 0.060 Kg @ ₹850/kg	Base: ₹1,200.00/kg Curr: **₹1,370.00/kg** RM Cost: **₹248.00 / pc**	**Precision CNC Facing & Chamfer** HT: **Stress Relief Annealed** Conversion: **₹62.00 / pc**	Surface: **10µ Dull Silver (IS 1374)** QA/MTC: EN 10204 Type 3.1, 99.9% IACS Packing: Anti-Tarnish Wrap + Heavy Box	**₹310.00** Ex-Works
2	**CNC Precision Rotor Turning Shaft OD 45×185mm** DWG: KS-2026-S12 Rev C Size: **OD 45mm x 185mm L**	**EN8D Forged (BS 970 080M40)**	Gross In: **4.40 Kg** Net Fin: **3.850 Kg** Scrap: 0.55 Kg @ ₹32/kg	Base: ₹280.00/kg Curr: **₹320.00/kg** RM Cost: **₹1,408.00 / pc**	**4-Axis CNC Turning & Keyway** HT: **Induction Hardened (Bearing)** Conversion: **₹842.00 / pc**	Surface: **Black Phosphated to IS 3618** QA/MTC: 100% UT Soundness & CMM Packing: VCI Sleeve + Pallet Crate	**₹2250.00** Ex-Works
3	**Laser Cut Transformer Mounting Bracket Plate** DWG: BRK-SS-2026-09 Size: **120mm x 90mm x 6.0mm Thk**	**SS 304 Stainless (ASTM A240 2B)**	Gross In: **2.10 Kg** Net Fin: **1.650 Kg** Scrap: 0.45 Kg @ ₹120/kg	Base: ₹310.00/kg Curr: **₹355.00/kg** RM Cost: **₹445.00 / pc**	**High-Pressure CNC Fiber Laser & Bending** HT: **Mill Annealed** Conversion: **₹305.00 / pc**	Surface: **ASTM A380 Passivation** QA/MTC: 96-Hr Salt Spray, MTC 3.1 Packing: Scratch-Proof Polyfilm Bundles	**₹750.00** Ex-Works
4	**Machined Phosphor Bronze Bush ID 35×50×60L** DWG: BSH-PB-104 Rev A Size: **ID 35 (H7) x OD 50 × 60mm L**	**PB2 Centrifugal Cast (BS 1400)**	Gross In: **1.20 Kg** Net Fin: **0.820 Kg** Scrap: 0.38 Kg @ ₹620/kg	Base: ₹1,050.00/kg Curr: **₹1,180.00/kg** RM Cost: **₹920.00 / pc**	**Precision Boring (H7 Fit) & OD s6** HT: **As Cast / Stress Relieved** Conversion: **₹230.00 / pc**	Surface: **Figure-8 Oil Grooved & Oiled** QA/MTC: 85 HB Min, H7 Plug Gauge Packing: Wax Paper Sealed in Poly Bag	**₹1150.00** Ex-Works
5	**Copper Terminal Busbar Link 40×5×150mm Plated** DWG: BUS-CU-55 Size: **40mm x 5.0mm x 150mm L**	**EC Grade Copper Strip (IS 1897)**	Gross In: **0.310 Kg** Net Fin: **0.268 Kg** Scrap: 0.042 Kg @ ₹850/kg	Base: ₹1,200.00/kg Curr: **₹1,370.00/kg** RM Cost: **₹367.00 / pc**	**Hydraulic Shear Cut & 2 Holes ø10** HT: **Half Hard (HB 75-85)** Conversion: **₹75.00 / pc**	Surface: **10µ Dull Silver (Anti-Tarnish)** QA/MTC: Silver Thk, 99.9% IACS Passed Packing: Layered Corrugated Separator Box	**₹442.00** Ex-Works
6	**Hardened Pinion Gear Shaft OD 60×220mm** DWG: SFT-EN24-88 Rev B Size: **OD 60mm x 220mm L**	**EN24 (817M40) Alloy Forged**	Gross In: **6.20 Kg** Net Fin: **4.950 Kg** Scrap: 1.25 Kg @ ₹45/kg	Base: ₹340.00/kg Curr: **₹410.00/kg** RM Cost: **₹2,312.00 / pc**	**CNC Turning, Hobbing & Spline** HT: **Hardened & Tempered 50-52 HRC** Conversion: **₹1,138.00 / pc**	Surface: **Manganese Phosphated IS 3618** QA/MTC: 100% MPI Crack Detection, CMM Packing: VCI Oil Dipped + Wooden Crate	**₹3450.00** Ex-Works

TERMS & SPECIAL TECHNICAL CLAUSES:

- **Commodity Price Variation Clause:** Metal prices linked to primary producer rates as on invoice date.
- **Quality Guarantee:** Manufacturing guarantee against metallurgical defects & dimensional deviations.
- **Certification:** 100% components inspected with MTC 3.1 & dimensional calibration reports.

FOR K.S. ENGINEERING WORKS

Technical & Works Manager